MYSORE CITY IMPROVEMENT TRUST BOARD.

Notice is hereby given that sealed tenders will be received at the office of the Chairman, City Improvement Trust Board, Mysore, upto 15th March 1917, for "Construction of the Municipal Office Buildings in Mysore." An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

The plans, detailed estimates and conditions which are subject to eventual alterations may be seen in the Chairman's office, *i.e.*, Rangacharlu Memorial Hall, Mysore, on any day during the office hours.

Tenders should be submitted on printed forms which may be obtained from the Chairman's office. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

Each tender must be accompanied by a deposit of Rs. 1,000 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for construction of the Municipal office Buildings in Mysore," in default of which, tenders will be rejected.

The final acceptance of any tender will rest with the Government of Mysore, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

Within a week of the acceptance of the tender, the successful tenderer will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

The name of the successful tenderer whose tender has been accepted, will be posted on the notice board in the Chairman's office in due course. No enquiries regarding the acceptance or rejection of any tender will receive any reply.

On acceptance of one of the tenders, the earnest money of rejected tenders will be returned.

Estimates for constructing the Municipal Office Building in Mysore.

No.	Items of work	Ground floor		First floor	
	Main Building.	Per	Quantity	Per	Quantity
1	Earthwork, excavation and refilling basement	C. yd.	868	...	...
2	Stone jelly concrete	C. ft.	8,974	...	...
3	Burnt brick in chunam, foundation and basement	"	22,660	...	...
4	Brick in chunam superstructure	"	20,738	C. ft.	24,614
5	Front screen wall of armoured brick work	S. ft.	257	...	...
6	Brick in chunam, arch work with foliation	C. ft.	1,291	C. ft.	755
7	Do segmental arch work...	"	822	...	...
8	Cement concrete bond slabs	"	76	...	...
9	Wire cut brick in chunam pillars	"	684	C. ft.	855
10	Burnt stone slabs, one line dressed, 6" thick	S. ft.	4,466	S. ft.	1,363
11	Plastering with chunam	Sqr.	316·20	Sqr.	304·61
12	White and colourwashing	"	316·20	"	304·61
13	Teakwood panelled door shutters, 1½" thick with towers at top panel of shutters including special fittings, etc., complete.	S. ft.	1,344	S. ft.	1,216
14	Teakwood door, 1/3 panel and 2/3 glazed shutters including special fittings.	"	256	"	256
15	Teakwood windows with panelled and glazed shutters, iron bars including special fittings; complete.	"	391	"	455
16	Teakwood glazed door and window tops, rectangular	"	494	"	484
17	Iron clamps for doors and windows	Each	312	Each	312
18	Flooring with Cuddapah slabs over 3" concrete and cement pointing ...	Sqr.	26·28	...	...
19	Flooring with Mangalore tiles over 3" concrete and cement pointing...	"	68·62	...	...
20	Teakwood work wrought and put including oiling	C. ft.	1047·70	C. ft.	1096·50
21	Pucka terrace, 9"	Sqr.	103·30	Sqr.	103·20
22	Forming bases of towers	R. ft.	244	...	...
23	Cornice, 12" including moulding at neck	"	336	R. ft.	350
24	Dental cornice, 15"	"	597	...	...
25	Forming bases and capitals of pillars including side pillars... ...	Each	48	Each	20
26	Forming foliation and plastering introdas of arches	"	44	"	20
27	Forming nitches, foliation and panels	"	4	...	...
28	Forming nitches	"	48	...	...
29	Forming panels and champering of arch-ways	"	44	...	...
30	Forming ornamental bases	"	28	Each	4
31	Boring girders of 24"×7½"	R. ft.	620	R. ft.	629
32	Painting doors and widdows with silicate paint	Sqr.	46·50	Sqr.	49·60
33	Plinth drain of cement concrete, 8'×8" with Cuddappah slabs alround	R. ft.	690	...	...
34	Teakwood staircase with Balustrade and tophand rail	Each	2	...	...
35	Spiral staircase in front of centre block, 5'—6" Diar.	"	2	...	...
36	Lavelling and clearing ground	Lump	sum	...	...
37	Teakwood glazed ventilators with special fittings	...	...	S. ft.	256
38	Teakwood frame and trellices works, etc., (centre block)	...	...	"	474
39	Flooring with Mangalore tiles over mortar bed and cement pointing	...	...	Sqr.	93·00
40	Forming panells of towers	...	...	Each	60
41	Do small panells of towers	...	...	"	60
42	Providing pillars, capitals and dome of front towers, complete ...	...	...	"	2

No.	Items or work	Store rooms		Latrines	
		Per	Quantity	Per	Quantity
43	Providing pillars, capitals, and dome of end towers complete ...	...	...	Each	8
44	Forming bases and capitals of half pillars in front and rear of end wings.	...	...	"	16
45	Forming nitches foliation and plastering introdas of arches ⅜" deep of end wings front and rear.	...	...	"	22
46	Forming and plastering the foliation of centre block front and rear ...	...	...	"	2
47	Cornice 6" top of ventilators	...	...	R. ft.	100
48	Burnt stones brackets including plastering	...	...	Each	237
49	Cuddappah slabs lovey 2"	...	...	S. ft.	922
50	Constructing vimanams of end wings	...	...	Each	4
51	Brick in chunam plain parapet plastering (1½×1½) binding wall ...	...	...	R. ft.	38
52	Ornamental parapet wall 3 feet high including pedastals and plastering	...	...	"	677
53	Zinc spouts 4" diar.	...	...	"	80
54	Teakwood panelled screens for partition	S. ft.	1,785	S. ft.	2,212

CONSTRUCTING STORE ROOMS, AND LATRINES OF SIX SEATS.

No.	Items of work	Store rooms		Latrines	
		Per	Quantity	Per	Quantity
1	Earthwork excavating and refilling basement	C. yd.	300	C. yd.	12
2	Stone jelly concrete	C. ft.	3,540	C. ft.	244
3	Burnt brick in chunam foundation and basement... ...	"	4,578	"	254
4	Brick in chunam superstructure	"	9,718	"	450
5	Do arch work	"	97	Nil	Nil
6	Burnt stone slabs roughly dressed	S. ft.	519	Nil	Nil
7	Plastering with chunam mortar	Sqr.	176·40	Sqr.	6·97
8	Teakwood doors panelled, complete	S. ft.	300	S. ft.	20
9	Teakwood windows with iron bars, etc., complete	"	261	Nil	Nil
10	Teakwood ventilators with glazed shutters, etc.	"	192	Nil	Nil
11	Teakwood shutters of arch way	"	402	Nil	Nil
12	Flooring with burnt stone slabs of 3" over sand	Sqr.	9·00	Sqr.	1·20
13	Flooring with Cudappah slab over 3" concrete and cement pointing ...	Sqr.	27·00	Nil	Nil
14	Madras old steel rail 22 feet long at Rs. 1½	Each	3	Nil	Nil
15	Teakwood work wrought and put up including oiling	C. ft.	519·0	Nil	Nil
16	Roofing with 1st class Mangalore Tiles over teak reepers and complete	Sqr.	75·69	Nil	Nil
17	Ridge tiles set in mortar	R. ft.	319	Nil	Nil
18	Chunam Borders	"	172	Nil	Nil
19	Teakwood shelf 1½" planks, pegs, etc.	S. ft.	405	Nil	Nil
20	Teakwood ornamental eave board	R. ft.	724	Nil	Nil
21	Teakwood finials big	Each	6	Nil	Nil
22	Do small pendants	"	20	Nil	Nil
23	White and colour washing	Sqr.	176·40	Nil	Nil
24	Painting doors and windows	"	34·00	Nil	Nil
25	Levelling ground and clearing site	Lump	sum	Nil	Nil
26	Burnt stone slabs 6" thick one line dressed	Nil	Nil	S. ft.	191
27	Curb stone dressed and top rounded off and fixed	Nil	Nil	R. ft.	22
28	Cement plastering ½" thick	Nil	Nil	Sqr.	8·97
29	Coping with brick in mortar 6" thick and plastered	Nil	Nil	R. ft.	36
30	Teakwood shutters 1" thick planks with frames and hinges, etc., complete.	Nil	Nil	S. ft.	68
31	Concrete drain 3"×6" and cement pointing	Nil	Nil	R. ft.	76
32	Roofing with stone slabs 3" thick laid flat with 3" concrete plastered over and pointed with cement cieling.	Nil	Nil	Sqr.	1·34
33	Buckets in latrines	Nil	Nil	No.	6
34	Iron tub cistern	Nil	Nil	"	1
35	Granalothic flooring of cement concrete	Nil	Nil	Sqr.	·63
36	Making holes in slabs of latrine	Nil	Nil	No.	6
37	Cement concrete for latrine floor	Nil	Nil	C. ft.	14
38	Tarring and white washing, etc., complete	Lump	sum	Lump	sum
39	Iron shutters in rear with iron work, clamps, etc., complete... ...	Nil	Nil	S. ft.	18
40	Plain cornice	Nil	Nil	R. ft.	55
	Constructing Compound Wall.				
1	Earth work excavation	C. yd.	37	Nil	Nil
2	Concrete for filling foundation	C. ft.	337	Nil	Nil
3	Burnt brick in mortar for foundation and basement	"	1,092	Nil	Nil
4	Super-structure burnt brick in mud	"	932	Nil	Nil
5	Coping with brick in mud with chunam plastering	R. ft.	426	Nil	Nil
6	Chunam plastering	S.qr.	50·53	Nil	Nil
7	Gate pillars	Lump	sum	Lump	sum

T. LAKSHMANA RAO,
Chairman.

MYSORE DIVISION.

Absract Notification.

The attention of the public is invited to the notification, dated published in the extenso on page 84, Part IV of the *Mysore Gazette*, dated 1st February 1917, calling for tenders for Improving Staff Quarters at Mysore.

S. H. LAKSHMINARASAPPA,
Assistant Engineer,
Headquarter Range, Mysore.